


ELECTRICAL PANEL M															
LOAD SERVED	CKT #	TYPE	BKR TRIP	WIRE SIZE	PHASE A	PHASE B	PHASE C	PHASE A	PHASE	PHASE C	WIRE SIZE	BKR TRIP	TYPE	CKT #	LOAD SERVED
HVAC UNIT-1, 8.5 TONS	1		40	#8	8800				9320		#8	40		2	HVAC UNIT-2, 9 TONS
	3		40	#8		8800			9320		#8	40		4	
	5		40	#8			8800			9320	#8	40		6	
	7		50	#6	10171						#10	30		8	
ELECTRICAL PANEL A	9		25	#10		5440			6212		#10	30		10	HVAC UNIT-3, 6 TONS
	11		20	#10			3641			6212	#10	30		12	
	13		10	#14	0				1500		#14	10		14	
SPAR	13		10	#14		0			1119		#14	10		14	PUMP 2 HP WATER SUPPLY PUMP 1.5 HP SPAR
	13		10	#14			0			0	#14	10		14	
TOTAL VA PHASE A					12856			17032						29888	
TOTAL VA PHASE B					14200			16651						30851	
TOTAL VA PHASE C								15532						27873	
TOTAL VOLT-AMPS															88612
DIVIDE TOTAL VOLT-AMPS BY SYSTEM VOLTAGE (PHASE TO PHASE)								240		AMPS		369			
DIVIDE AMPS BY 3 PHASE MULTIPLIER								1.732		3 PHASE AMPS		213			
TOTAL CONNECTED LOAD (AMPS)												213			
TOTAL CONNECTED LOAD (AMPS) @ 125%										266					
MAIN TYPE AND AMPERE RATING										479 - 500 AMP MCB					
PANEL FEEDER SIZE ~ SEE RISER DIAGRAM															

HOUSE AT SEABROOK				
NEC ART 220 LOAD ANALYSIS - 400 AMP 220/240 VOLT 3 PHASE 4 WIRE ELECTRICAL SERVICE				
ITEM	CONNL. LOAD (VA)	DEMAND F.	DEMAND LOAD (WATTS)	TOTAL (AMPS)
LIGHTING	19252	125%	24065	
WATER HEATERS	0	100%	0	
KITCHEN EQUIPMENT	3500	65%	2275	
DINNING EQUIPMENT	2000	65%	1300	
HVAC LOADS	72996	100%	72996	
SUB-TOTAL			100636	
LARGEST MOTOR	2619	125%	3273.75	
TOTAL @ 220/240V/3PH	75616		103909.75	157 - 160

# 1 PANEL SCHEDULE & SERVICE CALCULATION

Material	
Name	Watt
110V ELECTRICAL DUPLEX RECEPTACLE WATERPROOF/110V DUPLEX RECEPTACLE WITH GROUND FAULT CIRCUIT INTERRUPTER	20W
2X2 FT LED LIGHT FLAT PANEL	40W
CEILING FAN WITH LIGHT AND REMOTE	55W
CEILING VENTILATION BATHROOM EXHAUST FAN WITH LED LIGHT	50W
VANITY LIGHT FIXTURES ADJUSTABLE BATHROOM LED LIGHT	22W
4 INCH ULTRA THIN LED RECESSED CEILING LED LIGHT	10W

ELECTRICAL PANEL A															
LOAD SERVED	CKT #	TYPE	BKR TRIP	WIRE SIZE	PHASE A	PHASE B	PHASE C	PHASE A	PHASE	PHASE C	WIRE SIZE	BKR TRIP	TYPE	CKT #	LOAD SERVED
FIRST FLOOR OUTDOOR & UNIT-1	1		20	#14	2084			830			#14	10		2	HALLWAY N, POOL, BBQ, VERANDA
GROUND LIVING, DINING & BAR	3		20	#14		1780			3660		#12	20		4	FIRST FLOOR UNIT-2 & UNIT-3
GRO. ALL OTHERS	5		20	#12			2357			1284	#14	20		6	GROUND CINEMA, GUST & T-1, 2
GRO. P. BAD, PORCH, OFFICE, T-3	7		20	#14	1282			5975			#10	30		8	OUTBUILDING
TOTAL VA PHASE A					3366			6805							10171
TOTAL VA PHASE B						1780			3660						5440
TOTAL VA PHASE C							2357			1284					3641
TOTAL VOLT-AMPS															19252
DIVIDE TOTAL VOLT-AMPS BY SYSTEM VOLTAGE (PHASE TO PHASE)								240	AMPS					80	
DIVIDE AMPS BY 3 PHASE MULTIPLIER								1.732	3 PHASE AMPS					46	
TOTAL CONNECTED LOAD (AMPS)														46	
TOTAL CONNECTED LOAD (AMPS) @ 125%									58						
MAIN TYPE AND AMPERE RATING								104 ~ 110 AMP MCB							
PANEL FEEDER SIZE ~ SEE RISER DIAGRAM															



1 SINGLE LINE DIAGRAM  
E200

## NOTES

Contractor to check all dimensions and levels on site prior to commencement of construction work on site.

Any discrepancies or variations are to be notified to the Designer before work commences.

Do not scale drawings for measurement

This drawing and copyrights therein are the property of Designer and may not used or reproduced without his consent

Foundations, floors, walls, roof and stairs construction to  
Structural Engineer's Design and Details

Rev	Description	Drawn By	Date
<p>Drawing Title</p> <p><b>GROUND &amp; FIRST FLOOR ELECTRICAL LAYOUT PLANS</b></p>			
<p>Project</p> <p><b>MARK STEVEN HOUSE</b> <b>CARDIFF HALL, ST. ANNS</b></p>			
<p>Signature</p>		<p>Date</p> <p><b>AUGUST 2023</b></p>	
<p>Drawn By: MM</p>			
<p>Checked:</p>			
<p>Authorised:</p>			
Project No.	Drawing Status	Scale (at A1)	
JAM/232	CONCEPT DESIGN	1 : 100	
<p>Drawing No</p> <p><b>JAM/276/03</b></p>			<p>Revision</p>